







iBox to Utility Distribution Box (on grid)		20m	20m	20m	20m	20m	20m	20m	20m
iBox to Utility Distribution Box (back up)		20m	20m	20m	20m	20m	20m	20m	20m
Inverter PE		20m	20m	20m	20m	20m	20m	20m	20m
Battery PE		20m	20m	20m	20m	20m	20m	20m	20m
ibox PE		20m	20m	20m	20m	20m	20m	20m	20m
PV Roof Grounding		20m	20m	20m	40m	40m	40m	40m	60m
Communication Cable		6m	6m	6m	6m	6m	6m	6m	6m
Photovoltaic DC cable connection terminal/pair		6	6	6	6	6	12	12	12
Rail H40/suit 2.4m		8	10	12	14	16	20	24	30
Rail Splice/suit		6	7	9	9	11	14	18	22
Hanger Bolt/suit		24	28	32	40	44	56	64	80
Universal Clamp Kit/suit		20	27	31	39	43	54	62	77
End Cap/suit		8	12	12	12	18	18	24	24
Grounding Lug/suit		4	4	4	4	6	10	10	12
Cable Clip/suit		10	11	14	16	18	22	27	33
Earting Clap/suit		16	18	22	25	29	36	44	55